



Project Strengthening Institutional and Economic Resilience in Yemen (SIERY)

مشروع / تعزيز المرونة المؤسسية والاقتصادية في اليمن (SIERY)

BOQs for equipping, and furnishing an obstetric emergency department in Al-Ara hospital -Al Madaribah, Al Ara District, Lahj Governorate.

جدول الكميات والمواصفات لتجهيز وتأثيث قسم طوارئ الولادة بمستشفى رأس العارة – مديرية العارة والمضاربة - محافظة لحج



Project Strengthening Institutional and Economic Resilience in Yemen (SIERY)

مشروع / تعزيز المرونة المؤسسية والاقتصادية في اليمن (SIERY)

BOQs for equipping, and furnishing an obstetric emergency department in Al-Ara hospital -Al Madaribah, Al Ara District, Lahj Governorate.

جدول الكميات والمواصفات لتجهيز وتأثيث قسم طوارئ الولادة بمستشفى رأس العارة – مديرية العارة والمضاربة - محافظة لحج

تعليمات عامة:

يجب علي المقاول تقديم خطة تفصيلية لتنفيذ الاعمال مع مراعاة الفترة الزمنية باقل فترة ممكنة لتنفيذ الاعمال من خلال تكثيف فرع العمل وبما لا يخل بالجودة.
علي المقاول تقديم جميع الكتلوجات وصور ومواصفات المواد والمعدات التي سيقوم بتوريدها ورافقها ضمن وثائق العطاء.

المقاول مسؤولاً عن تقديم دورة تدريبية تركز علي تشغيل الأجهزة الطبية وإدارتها، ويجب ان يقترح المقاول نطاق التدريب والجدول الزمني ويوافق عليه الاستشاري.

المقاول مسؤول عن صيانة الاجهزة لمدة عام بما في ذلك زيارات الصيانة الوقائية.

يجب ان يتم تصنيع جميع المعدات الموردة من قبل مصنعين عالميين مشهورين وذات جودة عالية درجة أولى ومعايير معتمدة وشهادة اختبار من طرف ثالث مستقل ويجب أن يكون جميع المواد والمعدات مدعومة بكافة التفاصيل والبيانات الفنية وعلي احضار عينات قبل التوريد لاعتمادها من قبل المهندس الاستشاري ولن تقبل أي مواد لم يتم اعتمادها مسبقاً.

المقاول مسؤول عن صيانة الاجهزة لمدة عام بما في ذلك زيارات الصيانة الوقائية.

Project Strengthening Institutional and Economic Resilience in Yemen (SIERY)
مشروع / تعزيز المرونة المؤسسية والاقتصادية في اليمن (SIERY)

BOQs for equipping, and furnishing an obstetric emergency department in Al-Ara hospital -Al Madaribah, Al Ara District, Lahj Governorate.

جدول الكميات والمواصفات لتجهيز وتأثيث قسم طوارئ الولادة بمستشفى رأس العارة - مديرية العارة والمضاربة - محافظة لحج

No	Item Name	الوحدة Unit	الكمية Qty	سعر الوحدة Unit Price\$	إجمالي السعر Total USD\$
1	Syring Pump W/Holder		1		
2	Infusion Pump W/Holder		1		
3	Ventilator Machine		1		
4	Mobile Electric Suction Machine 2X2 L		2		
5	Defibrillator With ECG Monitor		1		
6	Oxygen Concentrator		2		
7	Ultrasonic Nebulizer Portable		1		
8	Suture Instruments and Dressing Set		1		
9	Semi Automated Biochemistry Analyzer		1		
10	Automatic Heamatology cbc Complete Blood Cell Counter		1		
11	Patient Wheel Chair		1		
12	Delivery Set , Forceps		1		
13	Circumcision Instruments Sets+Sundries		1		
14	Gyn Examination Set		1		
15	Vaginal Speculum Set		1		
16	Tray Sterilization (standard)		1		
17	Kidney Basin, 25 cm, 825 ml, Stainless Steel		1		
18	Tray Instrument With Lid st.st		1		
19	Midwife Kit		1		
20	Instrument Trolley		1		
21	Infant Bassinet Bed		1		
22	Examination Gynecology Coach With Accessories		1		
23	Stainless Steel 3 Seats Hospital Waiting Chair		2		
24	Ambu Bag Resuscitation Set (infant)		1		
25	Ambu Bag Resuscitation Set (Adult)		1		
26	Oxygen Cylinder 40L With Oxygen Regulator, Humidifier and Trolley		2		
27	Infrared Medical Thermometer		1		
28	Vital Signs Monitor with Mobile Stand		1		
29	Fetoscope - Audio Fetal Doppler		1		
30	Infant Incubator		1		
31	Phototherapy Unit		1		
32	Infant Warmer		1		
33	Hand Held Pulse Oximeter		1		
34	Thermometer Digital		5		
35	Split Unit Air Conditioner 2 Ton		1		
36	Training Course on the Use of Medical Equipment: This item includes providing a comprehensive training course for all concerned employees, not exceeding 5 persons approved by the center's management in the medical center, on how to use the medical equipment to be provided to the center. Training Objectives: The training course will cover an introduction to the equipment and its purposes of use, how to set it up and operate it properly, and routine maintenance guidelines to ensure optimal operation. The course will also include teaching safety rules to avoid accidents and injuries, and providing instructions on how to deal with common problems and emergency malfunctions. An interactive session will be organized to allow employees to try the equipment under the supervision of a certified trainer. Training Content: Must be approved by the supervising engineer. Training Duration: The training duration is 15 hours, divided into 3 days, 5 hours per day. Trainers: Must be specialized in the field of medical laboratories, have experience in using laboratory equipment and tools, and excellent training skills. Meals: The supplier must provide a daily lunch for the trainees.	L.S	1		

Project Strengthening Institutional and Economic Resilience in Yemen (SIERY)
مشروع / تعزيز المرونة المؤسسية والاقتصادية في اليمن (SIERY)

BOQs for equipping, and furnishing an obstetric emergency department in Al-Ara hospital -Al Madaribah, Al Ara District, Lahj Governorate.

جدول الكميات والمواصفات لتجهيز وتأثيث قسم طوارئ الولادة بمستشفى رأس العارة – مديرية العارة والمضاربة - محافظة لحج

No	Item Name	الوحدة Unit	الكمية Qty	سعر الوحدة Unit Price\$	إجمالي السعر Total USD\$
37	<p>Project Signboard : In number: Supply and installation of a metal Signboard in the name of the project in the dimensions shown in drawing and the price includes the following:</p> <ul style="list-style-type: none"> - Digging soil depth of 60 cm for the two bases then the pouring of plain concrete and water treatment period required- Implementation of two concrete footings in dimation (50X50) cm and a depth of 40 cm of 0.8 m3 aggregate and 0.4m3 sand with 250 kg\m3 cement with water treatment and all necessary - Galvanized Steel Pipe Plates 2.5", it is covered from above with a tight cover ,and at the bottom two metal bars with diamter of 16mm,30cm long , which are painted a resistant paint 3 faces,well bonded with two + shaped welds and are fixed at the bottom of the base before casting. - Supply and installation of metal sheets (sheets) Made of heavy black iron,1.5mm thick and distribution shown in the model With internal strengthening in the space so that no traces appear on the painting, and so that the pieces of the painting are welded from all sides so that no space (filled with putty) is left for rain water to enter. - Painting of writing boards and standing with a resistant paint 3 faces and then painting the writing boards With putty, foundation and fire paint in the specified color 3 faces to getting smooth surface with out any roughness. - Writing on the painting in clear script, distinctive writing and color specified in Arabic and English With fiery paint, and the writing is on two sides in white. - Install the Signboard in the appropriate place determined by the supervisor and the price includes the supply and installation and all necessary for it to work <p>The price include all works to finish this item according to drawings, specifications, the technical asset & workmanship, general & specific conditions and instructions of the supervisor engineer</p>	NO	1		
Estimated Cost \$					